

A) Quotations can be submitted on or before 30/07/2021 till 4:00 pm on Working days.

B) Details of Work to be done.

1. Front Glazing , other windows and glasses of ETC Building.

- i) Front Glazing Frame Repair and Re- fixing of glasses expenditure Rs. .... Cost (including frame, all material, Scaffolding and Labour)
- ii) Other Windows & Glasses (5 mm Entilo blue Toughened Glass)

| S.No.        | Location                           | No. of Windows & Glasses | Size           | Area                  |
|--------------|------------------------------------|--------------------------|----------------|-----------------------|
| 1.           | 1 <sup>st</sup> Floor Room No. 124 | 01                       | 3.270'x 3.75'  | 12.262 sqft.          |
| 2.           | 6 <sup>th</sup> floor Class Room   | 01                       | 3.66 'x 4.33'  | 15.847 sqft.          |
| 3.           | Stairs window                      | 03                       | 4.083'x 1.416' | 5.78 X 3= 17.34 Sqft. |
| 4.           | 4 <sup>th</sup> floor room No. 420 | 01                       | 5.166'x 3.66'  | 18.90 sqft.           |
| <b>Total</b> |                                    | <b>06</b>                |                | <b>64.349 sqft.</b>   |

65 sqft. @ Rs. ..../- per sqft., Total Rs. ..../-

2. Glazing and Windows of Academic Block.

- i) Structural Glazing Frame repair cost Rs. .... (cost including frame, all material, Scaffolding and Labour)
- ii) Windows/ Glasses (6mm ET 725 Cool lite Toughened Glass)

| S. No.       | Location                                      | No. of Windows & Glasses | Size  | Area                           |
|--------------|---|--------------------------|---|--------------------------------|
| 1.           | G. F. Reception                               | 02                       | 3.5'x3.66', 3.5'x3.75'                            | 12.81+13.125= 25.935 sqft.     |
| 2.           | 1 <sup>st</sup> Floor, Room No. 104, 115      | 02                       | 2.583'x6.166', 2.416x6.583'                       | 15.926+15.90= 31.826 sqft.     |
| 3.           | 2 <sup>nd</sup> Floor, Porch, Door & Corridor | 04                       | 3.583x6.166', 3.083'x3.416', (3.33'x5.25'-02 pc.) | 22.09+10.53+34.965=67.585sqft. |
| 4.           | 3 <sup>rd</sup> floor, Corridor               | 03                       | (3.583'x 5.208',-02pc), 3.375'x 5.208'            | 37.320+8.583= 45.903 sqft.     |
| 5.           | 4 <sup>th</sup> floor, corridor               | 10                       | 5.291'x3.541', (3.375'x 5.166'-09pc)              | 18.735+ 156.91= 175.645 sqft.  |
| 6.           | 5 <sup>th</sup> floor, Corridor               | 03                       | (2.5'x6.166'-02pc), 5.291'x3.541'                 | 30.83+18.735= 49.565 sqft.     |
| 7.           | 7 <sup>th</sup> floor Corridor                | 05                       | 5.291'x 3.541'-05pc                               | 93.677 sqft.                   |
| 8.           | 8 <sup>th</sup> floor corridor                | 02                       | 2.5'x6.166'-02pc                                  | 30.83 sqft.                    |
| <b>Total</b> |   | <b>31</b>                |   | <b>520.966 sqft.</b>           |

521 sqft. @ Rs. ..../- per sqft., Total Rs. .... /-

\* Glass Make- Saint Gobain

3. Doors and Structural Glazing of Girls Hostel.

- i) Iron Doors 5'4"x 8'6" (set of two doors) Total No. of Doors- 16 doors  
**# Specifications-** Angle 5mm 1½" X 1½", Section Pipe- 16 Gauge 2½ "X 1¼",  
Sheet- 16 gauge, Square bar grill 12mm with vertical 4" c/c & horizontal 2 grills  
(5'4" X 16") with wire mesh.  
Paint- Brown.  
Cost of door @Rs. ....../- per door.  
Total= Rs. ....../-

\* Specifications for door-

- ii) Structural Glazing of Girls Hostel. (Refilling of Silicone)  
Total Cost Rs. ....../-  
(cost including all material and Labour)

4. False Ceiling of ETC, Academic Block and Girls Hostel.

- i) Academic Block  
a) Total Area = 416 sqft. (complete work including all material, Tiles & labor)  
b) Only Tiles- 100 Tiles (Acoustic Tiles, Size-2'x2')

**# Terms & Conditions-**

1. Time period for completion of work- 2 months.
2. Payment- 35% advance, 35% after received of material at site, balance 30% after completion of work.

C) For more Details visit university during working hours.

**# Contact -**

Harjotpal Singh Dhillon (J.E. civil)  
Mob. No.- 87290-00882  
SGGSWU, FGS.